

National Infrastructure Corp. Ltd.

GSTIN 19NAICC441701Z1 · Final Bill with Measurement Annexure

FINAL RUNNING ACCOUNT BILL

Contract #74 · Public Health Engineering Dept, West Bengal · 17 RA bills

FIN/74

March 31, 2026

PART I — CONTRACT ABSTRACT

<i>Awarded Value</i>	INR 152.82 Cr
<i>Total Value of Work Billed</i>	INR 97.45 Cr
<i>Period</i>	August 9, 2021 — January 30, 2023

PART II — BOQ-WISE SUMMARY (AS EXECUTED)

Item	Description	Unit	Rate	BOQ Qty	Executed Value
1	Earthwork in excavation & embankment	cum	235	606278.434	142,475,432
2	Granular sub-base (GSB)	cum	1,242	99565.238	123,660,025
3	Wet mix macadam (WMM)	cum	1,775	81258.418	144,233,692
4	Dense bituminous macadam (DBM)	MT	5,976	18836.569	112,567,334
5	Bituminous concrete (BC)	MT	6,160	10108.926	62,270,986
6	RCC M30 for structures	cum	8,661	18127.49	157,002,191
7	Reinforcement steel Fe500	MT	70,747	1005.885	71,163,344
8	RCC kerb & channel	rmt	552	291955.603	161,159,493
Total					974,532,497

PART III — BILL-WISE ABSTRACT

RA	Bill No	Date	Value of Work	Cumulative
1	AR-2021-00389	2021-09-07	57,325,441	57,325,441
2	AR-2021-00390	2021-10-07	57,325,441	114,650,882

3	AR-2021-00391	2021-11-06	57,325,441	171,976,323
4	AR-2021-00392	2021-12-06	57,325,441	229,301,764
5	AR-2022-00393	2022-01-05	57,325,441	286,627,205
6	AR-2022-00394	2022-02-04	57,325,441	343,952,646
7	AR-2022-00395	2022-03-06	57,325,441	401,278,087
8	AR-2022-00396	2022-04-05	57,325,441	458,603,528
9	AR-2022-00397	2022-05-05	57,325,441	515,928,969
10	AR-2022-00398	2022-06-04	57,325,441	573,254,410
11	AR-2022-00399	2022-07-04	57,325,441	630,579,851
12	AR-2022-00400	2022-08-03	57,325,441	687,905,292
13	AR-2022-00401	2022-09-02	57,325,441	745,230,733
14	AR-2022-00402	2022-10-02	57,325,441	802,556,174
15	AR-2022-00403	2022-11-01	57,325,441	859,881,615
16	AR-2022-00404	2022-12-01	57,325,441	917,207,056
17	AR-2022-00405	2022-12-31	57,325,441	974,532,497

PART IV — MEASUREMENT ANNEXURE (ITEM-WISE, ALL BILLS)

ITEM 1 — EARTHWORK IN EXCAVATION & EMBANKMENT (CUM @ 235)

RA	Location / particulars	N	L	B	D	Qty	Amount
2	Reach R-8	3	31.82	7.52	18.901	13568.257	
2	Reach R-8	3	27.41	10.77	4.293	3801.954	
2	Reach R-8	4	33.23	9.38	9.087	11329.577	
2	Reach R-8	4	25.77	8.69	4.508	4038.11	
2	Reach R-8	4	23.28	6.17	19.884	11424.36	10,378,138
3	Structure S-13	2	14.45	1.06	152.308	4665.803	
3	Ch. 5+762 to 17+718	2	33.16	1.54	29.76	3039.472	
3	Reach R-3	4	19.11	7.3	6.486	3619.266	
3	Ch. 5+762 to 17+718	1	25.2	0.36	551.794	5005.875	3,837,604
4	Ch. 5+012 to 11+921	4	27.47	8.24	6.175	5590.914	
4	Grid 1-A / level 2	5	24.85	1.67	22.519	4672.636	
4	Grid 1-A / level 2	5	10.4	3.64	11.245	2128.454	
4	Structure S-8	2	30.36	1.06	49.884	3210.694	
4	Structure S-8	2	18.39	8.9	21.438	7017.558	
4	Ch. 5+012 to 11+921	5	19.66	9.13	4.92	4415.597	
4	Grid 1-A / level 2	6	2.36	5.65	74.169	5933.817	7,747,978
6	Grid 9-F / level 4	2	35.6	9.7	7.28	5027.859	
6	Structure S-8	6	8.7	3.0	25.701	4024.777	
6	Reach R-6	1	15.06	6.14	67.169	6211.01	
6	Structure S-8	3	28.02	0.98	94.809	7810.252	
6	Reach R-6	4	27.83	3.44	6.218	2381.126	
6	Grid 9-F / level 4	5	24.1	1.64	38.696	7647.104	
6	Grid 9-F / level 4	1	11.29	2.1	293.039	6947.662	

6	Reach R-6	6	38.35	8.11	2.439	4551.445	10,481,290
7	Reach R-3	1	26.07	6.57	42.476	7275.285	
7	Reach R-3	4	30.0	6.69	4.613	3703.316	
7	Structure S-21	4	18.38	2.12	34.055	5307.894	
7	Grid 8-F / level 4	2	35.42	11.26	14.222	11344.298	
7	Structure S-21	1	39.84	4.08	44.209	7186.049	
7	Reach R-3	2	3.11	4.74	288.223	8497.621	
7	Reach R-3	5	16.39	8.03	12.555	8261.924	12,120,376
10	Grid 8-B / level 3	4	28.41	4.09	7.591	3528.203	
10	Grid 8-B / level 3	5	13.26	1.11	47.525	3497.507	
10	Ch. 4+608 to 11+061	6	8.0	1.35	49.874	3231.835	
10	Structure S-5	2	25.0	11.75	6.204	3644.85	
10	Ch. 4+608 to 11+061	6	2.43	5.11	23.149	1724.688	
10	Ch. 4+608 to 11+061	3	20.1	11.32	3.995	2726.971	
10	Reach R-8	2	26.27	7.22	4.235	1606.5	
10	Structure S-5	4	2.02	1.5	248.688	3014.099	5,399,087
12	Reach R-4	5	12.7	0.9	112.907	6452.635	
12	Grid 5-E / level 1	6	29.27	10.86	6.69	12759.39	
12	Grid 5-E / level 1	4	27.34	2.98	45.345	14777.609	
12	Reach R-4	6	12.61	5.29	27.273	10915.784	
12	Grid 5-E / level 1	6	8.23	8.11	15.289	6122.813	
12	Ch. 9+051 to 10+803	6	9.34	1.74	68.248	6654.835	
12	Grid 5-E / level 1	6	16.79	3.34	16.67	5608.982	
12	Structure S-21	4	30.89	8.56	10.038	10616.928	17,368,615
15	Ch. 2+051 to 16+494	4	34.31	11.49	7.215	11377.244	
15	Structure S-3	6	8.26	7.25	14.707	5284.372	
15	Structure S-3	5	29.39	10.6	5.309	8269.67	

15	Ch. 2+051 to 16+494	6	3.17	9.54	50.399	9144.939	
15	Ch. 2+051 to 16+494	4	3.24	10.37	94.996	12767.006	
15	Grid 2-F / level 4	5	35.42	11.03	5.327	10405.831	13,453,538
16	Ch. 6+658 to 11+639	6	39.7	3.88	3.767	3481.522	
16	Structure S-15	1	9.73	7.17	56.447	3937.974	
16	Ch. 6+658 to 11+639	6	32.71	5.81	3.474	3961.3	
16	Ch. 6+658 to 11+639	3	3.73	2.05	171.4	3931.83	
16	Ch. 6+658 to 11+639	1	39.7	6.79	13.534	3648.266	
16	Reach R-9	2	2.7	8.23	58.307	2591.28	
16	Reach R-9	5	37.0	11.61	0.882	1894.404	
16	Structure S-15	4	20.68	10.2	1.634	1378.678	5,833,946
Item total (executed)						368598.178	86,620,572

ITEM 2 — GRANULAR SUB-BASE (GSB) (CUM @ 1,242)

RA	Location / particulars	N	L	B	D	Qty	Amount
1	Ch. 2+992 to 14+105	5	26.48	10.63	0.931	1310.301	
1	Reach R-3	1	10.28	8.64	20.002	1776.562	
1	Ch. 2+992 to 14+105	1	11.25	1.46	57.172	939.05	
1	Structure S-8	6	19.49	6.25	3.325	2430.159	
1	Grid 3-D / level 4	5	18.22	9.84	1.611	1444.139	
1	Ch. 2+992 to 14+105	2	6.69	4.27	21.874	1249.718	11,364,304
2	Structure S-8	4	13.78	4.88	2.827	760.422	
2	Ch. 6+616 to 17+076	2	9.86	8.95	2.792	492.771	
2	Reach R-12	6	29.46	4.39	1.681	1304.416	
2	Ch. 6+616 to 17+076	5	8.62	2.01	6.057	524.724	
2	Ch. 6+616 to 17+076	3	20.73	11.9	1.213	897.694	
2	Ch. 6+616 to 17+076	3	10.86	9.94	2.58	835.521	5,980,559

3	Ch. 1+920 to 17+181	6	21.06	6.8	1.437	1234.739	
3	Ch. 1+920 to 17+181	5	25.55	10.02	0.526	673.309	
3	Structure S-12	3	20.69	5.39	2.819	943.117	
3	Reach R-7	6	38.81	7.54	0.488	856.813	
3	Grid 4-F / level 1	2	3.0	3.01	29.607	534.702	
3	Reach R-7	4	28.94	8.95	1.676	1736.423	
3	Ch. 1+920 to 17+181	6	29.93	8.85	0.394	626.178	
3	Ch. 1+920 to 17+181	1	33.87	11.7	3.646	1444.833	9,998,519
4	Reach R-7	4	22.17	4.28	3.56	1351.199	
4	Ch. 8+605 to 14+317	5	38.15	5.26	2.05	2056.857	
4	Grid 5-E / level 4	4	7.2	5.22	3.956	594.729	
4	Reach R-7	1	29.88	7.43	2.963	657.811	
4	Ch. 8+605 to 14+317	1	31.7	10.86	3.448	1187.015	7,262,853
5	Ch. 6+158 to 19+611	5	19.17	1.26	3.105	374.994	
5	Reach R-12	3	34.24	4.79	0.453	222.889	
5	Grid 6-E / level 4	3	33.75	0.64	6.982	452.434	
5	Ch. 6+158 to 19+611	4	3.08	6.81	4.168	349.692	
5	Structure S-12	3	14.65	7.75	1.166	397.154	
5	Reach R-12	2	26.16	5.64	0.618	182.362	
5	Grid 6-E / level 4	3	19.87	2.93	2.849	497.599	
5	Reach R-12	2	28.63	3.04	2.359	410.632	3,586,599
6	Structure S-13	5	14.75	3.6	11.962	3175.911	
6	Structure S-13	2	4.3	2.06	70.618	1251.068	
6	Ch. 9+135 to 11+889	1	30.15	0.38	126.918	1454.1	
6	Structure S-13	2	2.89	2.98	149.091	2568.003	
6	Grid 2-C / level 4	1	4.77	3.24	166.97	2580.488	
6	Grid 2-C / level 4	2	13.79	9.98	6.616	1821.043	15,960,538

7	Reach R-10	6	6.84	2.9	5.626	669.584	
7	Grid 7-F / level 2	1	5.65	8.12	15.483	710.329	
7	Ch. 9+804 to 15+924	4	23.65	3.55	1.393	467.811	
7	Ch. 9+804 to 15+924	1	19.51	8.3	5.263	852.253	
7	Reach R-10	2	10.95	2.29	14.93	748.754	
7	Grid 7-F / level 2	1	15.6	5.11	10.149	809.038	5,288,024
8	Reach R-1	6	26.17	6.13	1.25	1203.166	
8	Grid 9-A / level 1	1	19.76	8.73	9.414	1623.96	
8	Structure S-19	3	26.0	11.31	1.05	926.289	
8	Structure S-19	6	3.6	7.32	8.854	1399.924	
8	Reach R-1	1	19.73	3.48	39.511	2712.841	
8	Structure S-19	3	26.53	3.91	5.941	1848.821	
8	Grid 9-A / level 1	4	34.21	0.53	31.916	2314.714	14,941,112
11	Grid 6-F / level 1	4	27.0	3.98	6.674	2868.752	
11	Grid 6-F / level 1	2	33.67	11.8	3.447	2739.028	
11	Structure S-17	6	12.24	1.75	12.378	1590.821	
11	Structure S-17	5	38.22	6.89	1.469	1934.201	
11	Reach R-5	1	32.79	9.33	4.14	1266.553	
11	Structure S-17	4	32.54	1.33	6.785	1174.57	14,375,117
12	Grid 2-E / level 4	5	15.81	10.12	2.097	1677.571	
12	Structure S-15	1	2.31	3.52	163.678	1330.899	
12	Ch. 3+637 to 10+565	5	3.95	10.61	3.016	631.995	
12	Ch. 3+637 to 10+565	4	33.07	10.41	0.926	1275.134	
12	Ch. 3+637 to 10+565	3	21.12	10.45	1.406	930.929	
12	Reach R-1	1	28.49	6.82	9.363	1819.248	
12	Grid 2-E / level 4	1	14.3	8.13	16.096	1871.305	11,845,125
13	Ch. 0+031 to 19+304	5	12.02	4.75	10.471	2989.209	

13	Grid 3-C / level 1	6	5.73	8.03	12.575	3471.598	
13	Structure S-13	6	9.4	11.32	4.511	2880.039	
13	Grid 3-C / level 1	1	31.25	3.5	22.759	2489.266	
13	Structure S-13	3	14.65	10.85	6.315	3011.355	18,432,902
14	Grid 7-A / level 3	5	21.96	4.92	5.673	3064.645	
14	Reach R-2	5	6.46	10.59	4.684	1602.195	
14	Ch. 4+636 to 17+356	1	33.17	4.0	29.193	3873.327	
14	Ch. 4+636 to 17+356	2	25.16	6.09	8.919	2733.217	
14	Structure S-9	4	3.04	1.14	186.522	2585.643	
14	Structure S-9	3	14.05	2.6	17.977	1970.099	19,659,389
15	Grid 3-C / level 1	5	33.83	5.67	0.471	451.727	
15	Grid 3-C / level 1	4	31.68	5.15	1.925	1256.27	
15	Ch. 7+379 to 18+203	2	33.87	4.51	4.373	1335.984	
15	Ch. 7+379 to 18+203	2	3.87	6.37	18.154	895.061	
15	Structure S-17	4	38.92	2.23	2.825	980.745	6,110,611
17	Ch. 8+333 to 13+594	1	35.1	3.17	13.356	1486.082	
17	Reach R-6	4	16.7	1.64	9.599	1051.59	
17	Grid 1-F / level 4	2	23.55	10.27	3.004	1453.086	
17	Ch. 8+333 to 13+594	4	25.38	10.99	1.668	1860.996	7,268,100
Item total (executed)						122442.635	152,073,752

ITEM 3 — WET MIX MACADAM (WMM) (CUM @ 1,775)

RA	Location / particulars	N	L	B	D	Qty	Amount
1	Ch. 9+814 to 10+071	2	4.65	1.79	84.755	1410.916	
1	Ch. 9+814 to 10+071	2	15.19	3.6	7.48	818.073	
1	Structure S-3	1	26.95	2.39	17.545	1130.082	
1	Grid 4-D / level 1	1	9.47	10.06	8.531	812.733	7,405,018
3	Ch. 7+771 to 17+042	5	8.16	2.69	5.154	565.662	
3	Reach R-3	6	21.82	9.48	0.443	549.817	
3	Reach R-3	3	28.19	8.39	0.744	527.899	
3	Reach R-3	4	4.23	6.82	2.701	311.68	
3	Ch. 7+771 to 17+042	1	12.62	4.31	6.703	364.591	
3	Ch. 7+771 to 17+042	6	15.6	2.0	2.588	484.474	
3	Ch. 7+771 to 17+042	6	11.9	2.3	1.931	317.109	
3	Reach R-3	6	38.65	11.59	0.093	249.958	5,985,122
4	Ch. 3+260 to 11+149	1	37.46	6.26	3.5	820.749	
4	Structure S-13	6	7.02	3.93	3.17	524.735	
4	Reach R-9	1	8.42	9.4	14.981	1185.716	
4	Reach R-9	5	15.35	6.16	0.88	416.046	
4	Reach R-9	3	9.77	4.68	5.819	798.197	
4	Grid 1-C / level 4	3	26.53	0.94	7.013	524.675	
4	Reach R-9	1	4.75	11.26	15.551	831.745	9,055,730
5	Reach R-2	1	11.97	3.53	14.32	605.079	
5	Grid 6-C / level 2	4	31.12	8.6	1.662	1779.218	
5	Grid 6-C / level 2	4	10.32	0.69	53.085	1512.031	
5	Reach R-2	2	19.97	9.37	2.438	912.392	8,534,716
6	Reach R-2	4	23.36	9.3	0.882	766.451	

6	Grid 6-B / level 3	4	21.83	0.97	15.001	1270.591	
6	Reach R-2	4	23.72	2.17	6.85	1410.344	
6	Reach R-2	3	27.09	3.37	5.925	1622.738	
6	Structure S-12	1	6.59	11.18	21.992	1620.287	
6	Grid 6-B / level 3	4	22.95	10.46	1.705	1637.189	
6	Grid 6-B / level 3	6	12.79	3.7	2.451	695.932	16,015,843
8	Ch. 3+538 to 17+719	5	38.31	8.94	1.68	2876.928	
8	Structure S-19	4	20.31	3.96	7.231	2326.288	
8	Reach R-1	5	34.34	5.91	1.702	1727.099	
8	Reach R-1	6	21.58	9.15	1.037	1228.577	
8	Reach R-1	4	7.01	4.25	16.246	1936.036	17,920,858
9	Reach R-6	4	15.2	10.48	1.952	1243.783	
9	Structure S-17	3	21.5	8.61	1.51	838.571	
9	Structure S-17	3	24.95	9.43	1.229	867.472	
9	Reach R-6	4	39.54	0.55	13.97	1215.222	
9	Ch. 2+057 to 10+657	2	19.88	1.0	17.519	696.555	
9	Grid 2-D / level 1	2	23.51	5.9	3.138	870.538	10,175,281
10	Ch. 2+965 to 14+021	4	5.54	9.83	3.989	868.935	
10	Structure S-23	1	15.84	3.14	37.774	1878.788	
10	Grid 6-D / level 2	1	34.42	11.31	4.729	1840.953	
10	Grid 6-D / level 2	5	33.1	3.21	2.98	1583.14	
10	Reach R-1	6	20.61	5.58	1.038	716.244	
10	Grid 6-D / level 2	2	27.3	1.43	25.637	2001.686	
10	Structure S-23	5	32.99	6.66	0.718	788.771	
10	Ch. 2+965 to 14+021	1	11.09	9.78	17.013	1845.233	20,455,500
11	Grid 8-F / level 3	2	26.01	1.68	4.232	369.85	
11	Structure S-2	6	7.67	2.07	9.709	924.893	

11	Grid 8-F / level 3	3	20.99	3.75	4.257	1005.237	
11	Ch. 1+326 to 19+586	5	3.69	11.86	4.226	924.721	
11	Grid 8-F / level 3	5	17.39	10.15	1.176	1037.87	
11	Reach R-8	2	38.49	1.95	3.867	580.479	
11	Structure S-2	1	16.84	7.48	2.116	266.538	9,069,478
13	Structure S-3	4	16.08	10.87	1.368	956.449	
13	Ch. 2+381 to 13+885	4	22.99	9.11	0.896	750.629	
13	Structure S-3	5	26.97	7.48	0.536	540.651	
13	Structure S-3	1	12.43	10.51	5.658	739.157	
13	Ch. 2+381 to 13+885	4	11.64	2.46	4.711	539.587	
13	Grid 4-A / level 1	4	39.72	5.85	1.438	1336.546	
13	Reach R-3	4	5.27	1.8	20.144	764.344	
13	Reach R-3	5	29.07	10.22	0.613	910.597	11,603,740
14	Structure S-11	1	34.46	1.18	18.789	764.013	
14	Structure S-11	4	5.96	1.94	17.084	790.128	
14	Structure S-11	3	36.05	3.73	1.825	736.204	
14	Grid 6-C / level 2	6	27.72	4.85	1.344	1084.14	
14	Reach R-12	2	17.73	1.07	22.725	862.236	7,519,486
17	Reach R-8	2	16.54	11.77	2.796	1088.627	
17	Structure S-1	3	2.73	5.58	10.162	464.405	
17	Structure S-1	3	30.06	7.74	0.479	334.339	
17	Reach R-8	2	18.8	5.06	5.754	1094.733	
17	Reach R-8	1	28.08	2.59	15.636	1137.162	7,312,103
Item total (executed)						73832.606	131,052,875

ITEM 4 — DENSE BITUMINOUS MACADAM (DBM) (MT @ 5,976)

RA	Location / particulars	N	L	B	D	Qty	Amount
----	------------------------	---	---	---	---	-----	--------

1	Grid 1-E / level 2	2	9.08	10.55	0.341	65.332	
1	Ch. 2+419 to 11+391	3	2.37	10.08	1.907	136.672	
1	Grid 1-E / level 2	5	4.57	11.24	0.237	60.87	
1	Reach R-8	4	6.4	11.74	0.183	55.0	
1	Ch. 2+419 to 11+391	5	26.48	5.86	0.183	141.983	
1	Grid 1-E / level 2	3	21.97	3.84	0.525	132.875	
1	Ch. 2+419 to 11+391	1	29.28	0.45	8.106	106.805	
1	Structure S-1	3	29.71	1.42	1.0	126.565	4,934,736
2	Reach R-12	5	6.08	11.77	0.632	226.135	
2	Ch. 1+442 to 18+652	2	3.38	10.67	3.052	220.138	
2	Ch. 1+442 to 18+652	5	39.16	11.82	0.154	356.411	
2	Reach R-12	4	31.93	5.64	0.569	409.874	
2	Grid 1-B / level 4	4	24.62	2.52	1.186	294.329	
2	Structure S-5	4	30.8	4.04	0.646	321.532	
2	Reach R-12	1	39.9	8.84	0.459	161.897	
2	Reach R-12	3	18.52	4.14	1.89	434.735	14,496,788
4	Grid 4-D / level 2	2	11.49	11.99	0.508	139.969	
4	Ch. 4+718 to 15+864	3	10.74	2.89	1.416	131.852	
4	Reach R-11	3	7.95	2.49	4.224	250.849	
4	Structure S-6	2	12.6	9.61	1.504	364.227	
4	Ch. 4+718 to 15+864	3	22.85	4.35	0.852	254.06	
4	Structure S-6	6	25.59	8.79	0.141	190.296	
4	Ch. 4+718 to 15+864	5	25.98	6.87	0.254	226.673	
4	Grid 4-D / level 2	2	22.07	1.03	3.846	174.855	10,354,898
5	Reach R-2	4	18.39	9.03	0.174	115.579	
5	Structure S-5	2	14.24	8.81	0.803	201.48	
5	Structure S-5	5	21.6	6.61	0.296	211.308	

5	Grid 3-D / level 4	4	18.77	6.35	0.5	238.379	
5	Ch. 9+587 to 13+857	6	39.96	9.31	0.066	147.323	
5	Structure S-5	2	13.68	4.26	2.302	268.306	
5	Grid 3-D / level 4	6	13.44	10.59	0.273	233.136	8,460,919
7	Structure S-12	2	21.62	1.5	2.234	144.897	
7	Structure S-12	3	21.75	8.73	0.358	203.928	
7	Ch. 1+227 to 10+651	6	14.11	10.91	0.563	520.01	
7	Ch. 1+227 to 10+651	1	18.79	5.57	2.359	246.894	
7	Structure S-12	4	7.23	0.37	30.333	324.575	
7	Ch. 1+227 to 10+651	6	32.67	9.03	0.105	185.856	
7	Ch. 1+227 to 10+651	5	6.61	11.32	0.864	323.245	11,653,178
8	Ch. 2+474 to 17+096	3	12.4	0.94	18.267	638.76	
8	Structure S-10	4	17.09	1.86	2.093	266.124	
8	Ch. 2+474 to 17+096	2	3.2	9.71	8.45	525.117	
8	Structure S-10	4	12.42	6.94	1.319	454.764	
8	Structure S-10	6	26.63	3.92	0.384	240.514	
8	Reach R-4	2	19.76	7.98	0.924	291.402	14,442,185
9	Structure S-6	6	35.15	4.0	0.208	175.469	
9	Ch. 0+170 to 19+529	3	9.53	9.92	0.942	267.163	
9	Grid 9-C / level 2	5	28.71	8.23	0.144	170.124	
9	Reach R-8	6	5.49	4.75	1.708	267.242	
9	Ch. 0+170 to 19+529	4	18.55	9.51	0.238	167.943	6,260,147
11	Ch. 7+266 to 18+150	1	16.08	3.98	2.874	183.931	
11	Ch. 7+266 to 18+150	1	17.76	0.51	35.959	325.702	
11	Grid 5-D / level 2	3	37.9	1.49	1.715	290.543	
11	Grid 5-D / level 2	5	10.25	11.54	0.603	356.629	
11	Structure S-20	4	14.12	0.36	10.312	209.672	

11	Ch. 7+266 to 18+150	2	33.55	7.3	0.639	313.001	
11	Reach R-11	2	9.08	5.36	2.217	215.797	11,326,452
12	Grid 2-B / level 1	4	26.79	7.68	0.394	324.258	
12	Reach R-7	2	26.62	4.77	1.648	418.518	
12	Grid 2-B / level 1	5	13.66	11.41	0.371	289.121	
12	Reach R-7	1	26.42	3.05	5.688	458.345	
12	Structure S-13	5	21.75	7.77	0.249	210.402	
12	Ch. 6+047 to 13+036	1	36.72	7.36	2.203	595.381	
12	Reach R-7	5	31.54	6.46	0.537	547.064	16,985,072
15	Reach R-9	5	17.11	8.17	1.116	780.021	
15	Grid 6-F / level 4	1	36.71	11.26	2.123	877.552	
15	Structure S-10	6	7.35	9.87	2.425	1055.522	
15	Grid 6-F / level 4	1	8.79	0.69	119.653	725.707	20,552,494
17	Ch. 3+416 to 11+756	3	34.61	7.88	0.209	171.0	
17	Ch. 3+416 to 11+756	3	6.7	7.96	2.061	329.752	
17	Grid 5-C / level 1	2	18.78	9.36	0.769	270.351	
17	Ch. 3+416 to 11+756	2	38.85	2.41	0.939	175.834	
17	Structure S-20	3	18.7	1.72	1.754	169.247	6,670,770
Item total (executed)						21107.368	126,137,639

ITEM 5 — BITUMINOUS CONCRETE (BC) (MT @ 6,160)

RA	Location / particulars	N	L	B	D	Qty	Amount
1	Grid 3-B / level 4	5	27.61	6.11	0.254	214.245	
1	Structure S-16	1	37.35	6.07	1.191	270.017	
1	Reach R-10	1	7.84	7.34	2.159	124.241	
1	Reach R-10	3	10.75	7.57	0.935	228.264	
1	Grid 3-B / level 4	1	30.63	5.86	1.039	186.492	6,304,851
2	Ch. 3+283 to 11+864	3	20.8	5.59	0.912	318.12	
2	Structure S-17	3	33.87	9.49	0.537	517.818	
2	Reach R-4	4	20.33	5.79	0.505	237.776	
2	Reach R-4	3	38.14	4.18	0.341	163.092	7,615,336
3	Structure S-12	6	20.53	6.13	0.547	413.036	
3	Reach R-2	4	19.19	3.59	1.071	295.134	
3	Reach R-2	4	38.84	11.09	0.21	361.818	
3	Ch. 0+061 to 13+769	6	10.42	11.36	0.546	387.784	
3	Reach R-2	1	19.89	0.54	24.438	262.479	10,600,431
5	Grid 7-B / level 3	5	3.86	1.16	8.818	197.417	
5	Structure S-17	3	24.5	7.57	0.266	148.001	
5	Ch. 4+969 to 10+108	5	39.35	3.11	0.249	152.361	
5	Grid 7-B / level 3	2	29.28	8.11	0.296	140.577	3,928,738
8	Grid 4-A / level 2	4	7.6	6.21	1.377	259.956	
8	Grid 4-A / level 2	4	15.84	4.6	1.604	467.495	
8	Grid 4-A / level 2	1	9.21	10.77	4.742	470.367	
8	Structure S-17	4	27.4	11.76	0.333	429.202	10,021,286
9	Reach R-9	6	21.4	7.67	0.373	367.341	
9	Structure S-15	6	28.77	4.83	0.588	490.248	

9	Grid 4-C / level 1	3	28.79	2.89	1.003	250.358	
9	Grid 4-C / level 1	5	21.1	8.26	0.168	146.4	
9	Structure S-15	2	19.65	5.44	1.709	365.371	9,971,976
11	Reach R-8	5	3.3	6.42	0.695	73.621	
11	Grid 2-C / level 3	5	15.09	6.26	0.459	216.794	
11	Reach R-8	5	17.87	3.63	0.425	137.845	
11	Structure S-19	6	13.97	4.29	0.482	173.321	
11	Grid 2-C / level 3	1	32.69	5.01	0.949	155.424	
11	Reach R-8	1	13.68	10.15	1.574	218.553	
11	Grid 2-C / level 3	5	35.53	5.54	0.192	188.963	
11	Structure S-19	3	15.96	6.64	0.63	200.292	8,409,627
17	Grid 4-A / level 3	1	29.3	8.11	0.511	121.425	
17	Grid 4-A / level 3	1	8.23	11.61	0.527	50.355	
17	Structure S-12	5	7.22	11.12	0.127	50.982	
17	Grid 4-A / level 3	2	5.89	4.99	1.541	90.583	
17	Ch. 5+103 to 11+066	6	5.48	11.43	0.271	101.847	
17	Ch. 5+103 to 11+066	2	23.63	6.62	0.265	82.908	
17	Structure S-12	6	29.49	7.82	0.056	77.486	3,545,894
Item total (executed)						9804.892	60,398,139

ITEM 6 — RCC M30 FOR STRUCTURES (CUM @ 8,661)

RA	Location / particulars	N	L	B	D	Qty	Amount
1	Structure S-12	3	38.8	6.26	0.217	158.12	
1	Ch. 4+618 to 19+890	3	8.65	2.48	1.502	96.663	
1	Reach R-2	4	29.15	3.39	0.133	52.571	
1	Ch. 4+618 to 19+890	6	31.41	8.45	0.081	128.991	
1	Structure S-12	1	19.39	1.86	3.761	135.642	4,955,345

2	Ch. 8+047 to 13+362	2	16.44	2.31	5.582	423.969	
2	Ch. 8+047 to 13+362	6	18.1	11.49	0.166	207.137	
2	Grid 3-C / level 2	1	20.07	2.44	9.835	481.628	
2	Grid 3-C / level 2	4	27.4	7.57	0.681	565.007	14,532,981
3	Grid 8-D / level 1	2	19.97	6.74	0.964	259.505	
3	Ch. 0+751 to 11+531	5	22.9	8.09	0.286	264.923	
3	Grid 8-D / level 1	1	36.99	8.68	0.394	126.503	
3	Grid 8-D / level 1	6	7.02	7.32	0.513	158.167	
3	Ch. 0+751 to 11+531	5	23.93	10.73	0.203	260.62	
3	Reach R-12	1	38.18	3.82	0.483	70.444	9,868,397
4	Reach R-9	6	27.14	3.85	0.285	178.676	
4	Ch. 3+060 to 11+867	1	5.6	7.59	3.517	149.487	
4	Reach R-9	6	27.15	5.72	0.157	146.291	
4	Ch. 3+060 to 11+867	3	32.16	3.19	0.923	284.073	
4	Structure S-10	4	23.96	10.68	0.349	357.226	9,659,010
5	Ch. 1+003 to 10+200	1	12.94	7.57	2.279	223.241	
5	Ch. 1+003 to 10+200	3	31.77	0.92	1.415	124.075	
5	Grid 1-C / level 2	1	25.1	5.12	1.631	209.603	
5	Structure S-16	6	22.81	2.72	0.734	273.238	
5	Grid 1-C / level 2	5	3.25	7.29	0.671	79.488	
5	Ch. 1+003 to 10+200	1	16.04	9.0	0.972	140.318	9,095,132
6	Reach R-10	3	27.05	4.82	0.168	65.712	
6	Ch. 0+238 to 14+347	6	38.08	10.93	0.066	164.821	
6	Structure S-19	1	19.57	8.83	0.819	141.526	
6	Ch. 0+238 to 14+347	5	5.72	2.89	1.073	88.688	
6	Grid 6-F / level 4	4	19.71	6.63	0.27	141.131	
6	Structure S-19	5	35.8	2.3	0.462	190.205	6,863,175

7	Grid 2-A / level 3	3	25.92	11.55	0.145	130.229	
7	Grid 2-A / level 3	1	30.62	11.0	0.321	108.119	
7	Reach R-5	4	18.37	10.92	0.107	85.857	
7	Ch. 1+542 to 10+088	3	6.64	1.45	1.64	47.37	
7	Structure S-2	1	10.4	1.09	8.561	97.047	
7	Structure S-2	6	3.62	10.87	0.272	64.218	4,614,417
9	Structure S-23	3	32.79	11.2	0.143	157.549	
9	Reach R-6	2	28.1	2.43	0.725	99.01	
9	Ch. 1+478 to 17+170	3	16.96	0.8	3.913	159.275	
9	Reach R-6	5	7.48	11.45	0.567	242.806	
9	Grid 2-D / level 2	4	24.57	8.71	0.272	232.837	
9	Reach R-6	3	20.63	7.55	0.337	157.47	9,082,745
11	Reach R-1	2	15.87	6.87	0.75	163.54	
11	Structure S-13	1	35.67	6.28	1.719	385.069	
11	Ch. 6+444 to 18+749	3	6.81	7.58	2.092	323.966	
11	Ch. 6+444 to 18+749	4	4.89	8.6	2.037	342.656	
11	Reach R-1	1	20.93	8.22	1.092	187.873	
11	Ch. 6+444 to 18+749	5	28.6	5.14	0.313	230.061	14,144,767
13	Grid 8-A / level 3	5	24.95	2.26	0.763	215.116	
13	Structure S-21	3	27.8	1.04	2.488	215.799	
13	Ch. 9+738 to 14+773	6	38.04	6.88	0.248	389.432	
13	Ch. 9+738 to 14+773	4	32.46	1.82	0.829	195.9	
13	Grid 8-A / level 3	6	26.87	0.88	1.68	238.348	
13	Reach R-3	2	4.16	3.11	14.245	368.592	
13	Grid 8-A / level 3	5	25.46	7.73	0.207	203.694	15,825,100
16	Ch. 3+521 to 19+581	2	37.19	2.1	1.161	181.346	
16	Ch. 3+521 to 19+581	2	26.68	11.32	0.451	272.42	

16	Ch. 3+521 to 19+581	5	3.0	0.67	32.457	326.193	
16	Grid 2-C / level 1	6	25.5	1.13	2.915	503.974	
16	Grid 2-C / level 1	5	35.31	9.29	0.136	223.06	
16	Ch. 3+521 to 19+581	3	8.98	1.03	18.717	519.363	
16	Ch. 3+521 to 19+581	6	5.6	2.91	3.217	314.545	20,280,682
17	Grid 7-F / level 3	3	30.22	1.0	1.985	179.96	
17	Grid 7-F / level 3	1	2.82	10.57	5.102	152.077	
17	Grid 7-F / level 3	4	36.91	3.29	0.4	194.294	
17	Grid 7-F / level 3	3	20.75	1.85	1.293	148.905	
17	Structure S-1	1	11.51	10.92	1.433	180.113	
17	Reach R-2	5	8.54	7.8	0.536	178.52	
17	Grid 7-F / level 3	3	9.75	8.46	0.356	88.094	
17	Reach R-2	1	22.07	10.11	0.752	167.792	11,174,271
Item total (executed)						15020.902	130,096,022

ITEM 7 — REINFORCEMENT STEEL Fe500 (MT @ 70,747)

RA	Location / particulars	N	L	B	D	Qty	Amount
1	Grid 2-B / level 1	3	36.87	0.9	0.405	40.317	
1	Ch. 6+835 to 15+708	2	32.09	6.67	0.1	42.808	
1	Reach R-4	5	7.03	7.14	0.125	31.371	
1	Grid 2-B / level 1	5	11.47	5.29	0.152	46.114	11,366,829
3	Ch. 6+987 to 18+860	1	2.9	10.11	1.851	54.269	
3	Reach R-9	5	31.83	4.67	0.172	127.836	12,885,993
4	Reach R-5	4	12.05	7.71	0.285	105.912	
4	Grid 7-E / level 2	2	25.22	11.45	0.141	81.433	13,244,972
5	Structure S-19	3	19.07	2.74	0.246	38.562	
5	Ch. 3+516 to 10+741	4	36.46	4.44	0.088	56.983	
5	Structure S-19	5	20.22	8.4	0.062	52.653	
5	Grid 9-F / level 1	3	31.11	4.81	0.05	22.446	12,039,426
6	Reach R-2	3	33.05	2.32	0.217	49.916	
6	Reach R-2	1	29.37	5.89	0.162	28.024	
6	Reach R-2	4	5.28	8.96	0.187	35.387	8,004,595
7	Structure S-8	1	33.0	8.5	0.177	49.648	
7	Grid 5-D / level 4	5	19.65	8.48	0.064	53.322	
7	Ch. 6+840 to 18+936	6	35.49	5.32	0.05	56.642	10,798,316
9	Ch. 7+129 to 10+136	2	39.48	3.89	0.17	52.216	
9	Reach R-12	2	20.39	9.89	0.267	107.685	11,318,131
10	Grid 6-A / level 2	1	5.73	9.71	1.259	70.049	
10	Reach R-11	1	6.93	8.34	2.101	121.43	13,548,819
13	Reach R-4	4	22.61	4.2	0.312	118.513	
13	Grid 4-B / level 3	5	21.95	10.88	0.05	59.704	11,463,699

14	Structure S-22	3	22.07	11.85	0.095	74.536	
14	Ch. 1+284 to 12+352	2	36.3	11.22	0.05	40.729	
14	Grid 9-E / level 3	2	33.73	6.73	0.102	46.309	
14	Grid 9-E / level 3	6	26.5	8.68	0.05	69.006	14,446,971
15	Reach R-10	2	20.39	7.3	0.236	70.256	
15	Reach R-10	6	30.91	3.5	0.141	91.525	
15	Grid 4-C / level 3	2	39.6	6.28	0.164	81.57	17,208,798
16	Grid 3-A / level 3	3	20.26	0.6	1.624	59.224	
16	Grid 3-A / level 3	3	2.62	4.89	2.089	80.292	
16	Reach R-1	5	29.42	3.06	0.11	49.514	
16	Ch. 5+544 to 18+601	2	29.57	6.64	0.247	96.994	20,238,088
17	Structure S-4	3	11.59	7.13	0.198	49.086	
17	Ch. 1+551 to 13+353	1	36.37	1.48	1.016	54.689	
17	Structure S-4	1	10.46	10.13	0.488	51.708	10,996,223
Item total (executed)						2368.452	167,560,860

ITEM 8 — RCC KERB & CHANNEL (RMT @ 552)

RA	Location / particulars	N	L	B	D	Qty	Amount
1	Ch. 9+611 to 14+179	6	11.49	8.13	3.109	1742.539	
1	Grid 2-A / level 2	4	27.77	9.64	3.439	3682.52	
1	Grid 2-A / level 2	4	24.53	7.2	5.856	4137.053	
1	Ch. 9+611 to 14+179	6	19.59	7.94	1.996	1862.802	
1	Ch. 9+611 to 14+179	3	26.18	8.63	2.929	1985.277	
1	Reach R-12	6	6.7	4.29	12.524	2159.864	
1	Grid 2-A / level 2	3	8.9	0.63	83.87	1410.777	
1	Reach R-12	6	22.39	5.39	4.056	2936.92	10,994,358
2	Reach R-3	3	23.76	5.3	4.299	1624.093	

2	Grid 7-F / level 1	6	4.63	6.38	6.883	1219.918	
2	Reach R-3	4	8.87	6.95	12.545	3093.421	
2	Grid 7-F / level 1	3	33.91	2.74	6.786	1891.531	4,321,639
3	Ch. 8+295 to 10+025	1	36.88	8.16	4.239	1275.688	
3	Grid 1-B / level 2	3	34.44	6.14	2.414	1531.405	
3	Grid 1-B / level 2	5	4.7	7.09	18.67	3110.702	
3	Structure S-8	4	7.94	3.2	15.732	1598.875	4,149,375
5	Grid 1-F / level 4	5	24.85	2.64	11.368	3728.931	
5	Grid 1-F / level 4	6	23.52	9.01	3.386	4305.269	
5	Grid 1-F / level 4	3	2.37	11.18	20.311	1614.517	
5	Ch. 5+594 to 15+866	4	35.14	7.71	2.54	2752.643	
5	Structure S-24	4	34.42	11.07	3.048	4645.51	
5	Reach R-3	2	34.05	10.57	5.714	4113.034	11,679,911
7	Structure S-15	6	39.71	4.67	5.481	6098.567	
7	Grid 4-A / level 2	3	33.23	7.03	3.914	2743.012	
7	Structure S-15	3	33.52	9.19	7.311	6756.434	
7	Structure S-15	4	9.55	0.34	299.583	3890.984	
7	Reach R-8	6	22.2	5.98	4.76	3791.511	12,851,130
9	Structure S-12	3	4.63	1.91	71.232	1889.778	
9	Reach R-8	5	34.01	3.29	4.932	2759.279	
9	Grid 1-A / level 2	6	29.47	3.27	6.11	3532.811	
9	Structure S-12	1	11.99	9.0	30.114	3249.602	
9	Grid 1-A / level 2	1	35.67	4.11	22.783	3340.072	
9	Ch. 9+044 to 16+726	1	20.13	8.21	18.062	2985.058	
9	Grid 1-A / level 2	4	33.84	7.08	1.352	1295.688	10,517,161
10	Ch. 5+142 to 19+353	6	5.22	3.69	48.51	5606.34	
10	Structure S-7	1	31.44	10.98	9.528	3289.172	

10	Structure S-7	3	14.01	10.27	18.851	8136.998	
10	Ch. 5+142 to 19+353	6	21.75	6.36	5.68	4714.286	
10	Grid 5-E / level 1	3	39.21	1.88	16.078	3555.56	
10	Grid 5-E / level 1	6	5.55	6.39	14.277	3037.96	
10	Grid 5-E / level 1	1	23.87	3.43	50.408	4127.11	17,922,035
12	Ch. 7+184 to 10+767	3	32.64	2.48	14.711	3572.443	
12	Grid 9-E / level 1	2	30.2	11.94	3.461	2495.99	
12	Ch. 7+184 to 10+767	3	11.46	2.17	52.725	3933.528	
12	Structure S-17	6	36.17	6.19	3.106	4172.457	
12	Ch. 7+184 to 10+767	2	22.03	5.33	5.776	1356.435	
12	Grid 9-E / level 1	1	7.19	2.62	245.579	4626.168	11,126,629
14	Structure S-20	1	18.04	9.0	25.075	4071.177	
14	Reach R-10	5	2.39	3.48	90.763	3774.47	
14	Structure S-20	3	16.58	10.37	9.731	5019.287	
14	Grid 9-F / level 4	5	12.05	6.09	10.281	3772.33	
14	Structure S-20	5	35.22	6.22	3.342	3660.633	
14	Reach R-10	3	19.99	11.93	4.083	2921.15	
14	Structure S-20	4	8.51	0.55	161.828	3029.744	
14	Structure S-20	6	39.41	10.04	0.924	2193.63	15,699,595
16	Structure S-10	1	13.13	6.11	112.535	9028.042	
16	Reach R-1	6	10.42	3.53	23.107	5099.613	
16	Structure S-10	1	10.12	3.41	71.44	2465.337	
16	Reach R-1	5	38.59	9.14	1.863	3285.518	10,972,725
17	Structure S-17	3	24.13	2.17	22.884	3594.763	
17	Reach R-8	1	8.97	5.31	75.979	3618.933	
17	Grid 4-A / level 3	2	2.79	5.81	122.717	3978.461	
17	Reach R-8	4	27.06	9.6	2.378	2470.989	

17	Reach R-8	6	20.73	11.15	1.563	2167.626	
17	Ch. 2+809 to 19+849	4	37.79	10.73	0.659	1068.863	
17	Grid 4-A / level 3	3	35.12	2.18	8.115	1863.892	10,358,080
Item total (executed)						218464.925	120,592,638

Billing Engineer

Project Manager

For Public Health Engineering Dept, West
Bengal (accepted)