

# National Infrastructure Corp. Ltd.

GSTIN 19NAICC441701Z1 · Contractor's Bill

## RUNNING ACCOUNT BILL — RA 2

Contract #70 · Suvarna Projects Limited

Bill No: AR-2021-00344

Date: March 10, 2021

### ABSTRACT OF WORK DONE (THIS BILL)

| Item                            | Description               | Unit | Rate       | Qty (this bill) | Amount      |
|---------------------------------|---------------------------|------|------------|-----------------|-------------|
| 3                               | Wet mix macadam (WMM)     | cum  | 1,417      | 6108.159        | 8,655,261   |
| 5                               | Bituminous concrete (BC)  | MT   | 6,909      | 978.09          | 6,757,623   |
| 6                               | RCC M30 for structures    | cum  | 8,306      | 1223.235        | 10,160,189  |
| 7                               | Reinforcement steel Fe500 | MT   | 76,838     | 119.597         | 9,189,582   |
| 8                               | RCC kerb & channel        | rmt  | 526        | 17780.863       | 9,352,734   |
| 9                               | Road markings & signage   | LS   | 68,855,899 | 0.075           | 5,167,640   |
| Value of work done — this bill  |                           |      |            |                 | 49,283,029  |
| Add: GST @18%                   |                           |      |            |                 | 8,870,945   |
| Less: Retention @5.0%           |                           |      |            |                 | (2,464,151) |
| Net claimed (before client TDS) |                           |      |            |                 | 55,689,823  |

### CUMULATIVE POSITION

|                                        |            |
|----------------------------------------|------------|
| Value of work done up to previous bill | 49,283,029 |
| This bill                              | 49,283,029 |
| Cumulative up to & incl. RA 2          | 98,566,058 |

Prepared (Billing Engineer)

Checked (Engineer-in-Charge)